



CITY OF AMARILLO

DEPARTMENT OF BUILDING SAFETY

TO: Department of Building Safety Customers

SUBJECT: **INFORMATIONAL BULLETIN**

Alternate to installing a log lighter kit.

DATE: April 3, 2015

As in alternate to installing a log lighter kit, a licensed plumbing contractor may alter and install an appropriate length and type of pipe to function as a log lighter within the fire box.

Some acceptable methods would include a series of 1/8" holes or slots aligned along the upper quadrant of pipe and spaced 1 1/2" - 2" apart.

This shall be considered the Building Official's interpretation and policy per authority given under 2015 IBC section 104.1