





### **AUDITORIUM**



# Amarillo Civic Center Complex Auditorium 401 S. Buchanan Amarillo, Texas 79101



The Amarillo Civic Center Complex Auditorium is a proscenium theatre with no balcony. The theatre seats 2,310 with an additional 72 seats available on the orchestra pit if the orchestra pit is not in use. The fly system features thirty-seven single purchase and five double purchase lines. There are also five motorized electrics and one manually operated Grand Drape with travel in both directions. There are seven dressing rooms of various sizes located off-stage left. Loading on to the stage is done via backing down a 6 degree down ramp through a 28' wide x 14'1" high overhead door. There is about a 20' push from the standard height loading dock to the stage floor.

The Auditorium has a VerTek 4887 line array system with a center cluster. In addition, a thirty-two-channel Soundcraft mixer board and a 300' long, 40 channel; 8 buss audio snake with a 75 foot monitor split is available. CD players, microphones, cables, microphone stands and other audio/visual equipment are available on request. A Clear Com two channel headset system is in place, with jacks throughout the theatre and an HME wireless headset system that will interface with the system.

#### **Technical Specifications**

Revised 9/2/2022

#### Please Note the Following

- 1. No hang points house side of proscenium.
- 2. FOH snake run is minimum 275' along house right wall.
- 3. 5 Electrics Motorized (see line set) fly out to only 37'
- 4. Semi tractor/trailer rigs with large cabs may have problems backing to the dock. Please allow extra time for backing on the move-in.

#### STAGE MEASUREMENTS

Proscenium: 55' x 24'
Grand Drape to Back Wall 45' 02"
Grid Height 65'
Batten Length 68'

Arbor Set Capacity

800 lbs (Total Distributed on Batten on Acoustic Panel Battens, 600 lbs on all other non-motorized battens.)

Note: For any moving pipes that require more than 400 lbs. of weight please contact the Amarillo Civic Center Complex Production Management Team.

Fly Rail: 15' high off-stage right

Loading Galleries 2

Wing Space SL 19' 02"

SR 15' 04"

Stage Height from House Floor 3' 04"

Orchestra Pit Options 3' 01 3/4" Deep from house

floor

Cover to house floor

Overhead Stage Door (USL) 10' 02" Wide X 11' 02" High

Loading Dock Height 3' 10" (Truck Height)

Apron Down Stage of Grand Drape: 4'

Cross Over: Hallway behind upstage wall Stage floor Construction: Blonde Colored Wood sprung

floor.

#### LAGGING INTO THE STAGE FLOOR IS NOT ALLOWED!!!

#### **CONTACTS**

Derek Hisek William Weatherholt Cameron Cockrell
Production Manager Asst. Production Manager Asst. Production Manager

806-378-3088 806-378-9346 806-378-4211


<u>Derek.Hisek@amarillo.gov</u> <u>willian.weatherholt@amarillo.gov</u> <u>Cameron.cockrell@amarillo.gov</u>

#### **DRESSING ROOMS**

Upper level SL: 1 Large, 2 Medium, & 4 Small (all with toilets and showers) Lower level SL: (available only by special permission when no events are in Coliseum)

2 Large Locker Rooms / 2 Small (toilets and showers)

All dressing rooms have Live (Unrecorded) monitors that include stage video, stage audio, as well as back stage paging access (2 weeks notice for paging hook-up).



**Diagram of the Auditorium Dressing Room Area** 

#### STAGE LIGHTING

See lighting plan:

Lighting Control: ETC Element w/ 60 faders capable of channel mode or submaster mode.

Lighting Positions include, Ceiling Cove (AP) (40 circuits), 2 box booms (10 circuits each), 5 Motorized Electric Battens (35 circuits each), 5 Drop Downs SL & SR (6 Circuits each) 15 Floor packets (4 circuits each), 2 Wall Boxes (4 circuits each).

Dimmer & House Lighting Inventory available on request.

#### Follow Spots:

Four 2000 W. Xenon Super Troupers. House option of no more than 4 spots in the booth.

#### **Additional Show Power:**

2 – 600 amp (3 phase)

Bare Ends or 6 – 0 Camlock

Down Stage Left

1 – 200amp (3 phase)

Cam lock (Only) – independent Ground Down Stage Right – SOUND power

#### Audio: PA Array system

Vertek 4887 Line Array System Crown Micro Tech Amps Speaker Array:

2 top subs / 8 full range speakers per side, tuned and aimed to fill entire house area.

Flown out of sight line in front of Proscenium.

The Drive Rack for this system is tuned and locked by JBL. NO MODIFACATION of the system and its components is allowed in any way.

#### **Backstage Communication**

Clear Com two (2) channel wired headset system in place. HME wireless headset system available and will interface with Clear Com system.

#### Crew Rates:

Up Riggers \$37.00 per hour 4 hour minimum Down Riggers \$37.00 per hour 4 hour minimum

Crew Chief \$22.50 per hour

Runner Base Rate: \$150 per day plus expense. If runner is using a

personal vehicle price increases to \$180 per day plus


expenses.

Stagehands: \$17.00 per hour 2-hour minimum Crew Lead /Dept. Heads \$19.00 2 Hr. minimum

All labor calls that extend over 8 hours in a 24-hour day will be billed out at an overtime rate of time and a half.

#### **Stage Layout**

Included in the "Attachments" section of this PDF you will find an interactive version of this diagram allowing you to focus in on details and access the "Vectorworks" features. You must have Vectorworks loaded on your device to access these extra features, but it is not necessary to view the details of the standard diagram attachment.




# **Auditorium Line Set**

Lineset	Distance From		Stg.		House	
	Grand	Fire Curtain	Wgt. Size	House Hang	Goods Weight	Max Capacity
1	-4	3"	30 lbs	Grand Valance	240 lbs	620 lbs
2	0"	7"	Isolated	Grand Drape		N/A
3	2' 0"	2' 6"	20 lbs			620 lbs
4	2' 6"	3' 0"	20 lbs			620 lbs
5 1st Elec	DS: 3' 0" US: 4' 0"	DS: 3' 6" US: 4' 6"	N/A	1st Motorized Electric	N/A	2500 lbs
6	4' 6"	5' 0"	20 lbs	Orch Shell Cloud		620 lbs
7	5' 0"	5' 6"	20 lbs	1	450 lbs	620 lbs
8	5' 6"	6' 0"	20 lbs	1st Border	140 lbs	620 lbs
9	6' 6"	7' 0"	20lbs	1st Leg	160 lbs	620 lbs
10 2nd Elec	DS: 8' 0" US: 9' 0"	DS: 8' 6" US: 9' 6"	N/A	2nd Motorized Electric	N/A	2500 lbs
11	10' 0"	10' 6"	20 lbs			620 lbs
12	10' 6"	11' 0"	20 lbs			620 lbs
13	11' 0"	11' 6"	20 lbs			620 lbs
14	11' 6"	12' 0"	20 lbs			620 lbs
15	12' 0"	12' 6"	20 lbs			620 lbs
16	12' 6"	13' 0"	20 lbs	2nd Border	140 lbs	620 lbs
17	13' 0"	13' 6"	20 lbs	2nd Leg	160 lbs	620 lbs
18	13' 6"	14' 0"	30 lbs	Orch Shell Cloud 2	820 lbs	1300 lbs

Lineset	Distanc	ce From		House Hang		Max Capacity
35	27' 6"	28' 0"	20 lbs			
34	26' 6"	27' 0"	30 lbs	4th Leg	160 lbs	1300 lbs
33	25' 6"	26' 0"	20 lbs	4th Border	140 lbs	620 lbs
32	25' 0"	25' 6"	20 lbs			
31	24' 6"	25' 0"	30 lbs	Orch Shell Cloud 3	720 lbs	1300 lbs
30	24' 0"	24' 6"	20 lbs			
29	23' 0"	23' 6"	20 lbs		240lbs	620 lbs
28	22' 6"	23' 0"	30 lbs	Mid Stage Traveler	Curtain: 330lbs Track:	1300 lbs
27	21' 6"	22' 0"	30 lbs			1300 lbs
26	20' 6"	21' 0"	30 lbs			1300lbs
25 3rd Elec	DS: 18' 6" US: 19' 6"	DS: 19' 0" US: 20' 0"	N/A	3rd Motorized Electric	N/A	2500 lbs
24	17' 6"	18' 0"	20 lbs			
23	17' 0"	17' 6"	20 lbs	3rd Leg	160	620 lbs
22	16' 6"	17' 0"	20 lbs	3rd Border	140	620lbs
21	15' 6"	16' 0"	20 lbs			
20	14' 6"	15' 0"	20 lbs			620 lbs
19	14' 0"	14' 6"	20 lbs			620 lbs

	Grand	Fire Curtain	Stg. Wgt. Size		House Goods Weight		
36 4th	DS: 28' 6"	DS: 29' 0"	N/A	4th Motorized	N/A	2500 lbs	
Elec	US: 29' 6"	US: 30' 0"		Electric			
37	30' 6"	31' 0"	30 lbs				
38	31' 6"	32' 0"	30 lbs				
				Orch Shell Cloud		1200 lbc	
39	32' 6"	33' 0"	30 lbs	4	330 lbs	1300 lbs	
40	33' 0"	33' 6"	20 lbs				
41	34' 0"	34' 6"	20 lbs				
42	35' 0"	35' 6"	20 lbs	5th Leg	160 lbs	620 lbs	
43	36' 0"	36' 0"	50 lbs			Dbl Purchase	
44	37' 2"	37' 8"					
5th			N/A	5th Motorized	N/A	2500 lbs	
Elec	Single Baton			Electric			
45	39' 0"	39' 6"	20 lbs			Dbl Purchase Dbl	
46	39' 6"	40' 0"	50 lbs			Purchase	
47	40' 6"	41' 0"	50 lbs	US Full Black	660 lbs	Dbl Purchase	
48	41' 6"	42' 0"	50 lbs	Vinyl Cyc	300 lbs	Dbl Purchase	

## **House Floor Plan**



# **Dressing Rooms**

